# COUNTY OF SUFFOLK



STEVEN BELLONE SUFFOLK COUNTY EXECUTIVE

#### DEPARTMENT OF HEALTH SERVICES

GREGSON H. PIGOTT, M.D., M.P.H. Commissioner

January 20, 2023

Mr. Tamer Osman, P.E. Delta Specialty Precast Concrete Engineers 860 Hooper Road Endwell, NY 13760 Sent via e-mail: <u>precast@delta-eas.com</u>



#### Re: NS-003 Fuji Clean CEN 5 & CEN 7 HS-20 Topping Slab

Dear Mr. Osman,

The Suffolk County Department of Health Services, Division of Environmental Quality, Office of Ecology has received and reviewed your design computations prepared for Advanced Wastewater Solutions, Project No. 2023.030.001, with your signature and sealed on 1/19/2023 for the "CEN5/7 Precast Cover Slabs 10'-0" O.D.".

Based on the information provided, the Department of Health Services approves the use of this precast concrete structure as a top slab for precast concrete rings previously approved by SCDHS, SCDPW or NYSDOT in traffic areas with a maximum burial depth of 2-feet. A copy of this letter and the signed and sealed design report will remain on file in the Office of Wastewater Management for future reference.

If you have any questions, please do not hesitate to contact me at (631) 852-5811.

Sincerely,

Ken Zegel, P.E. Principal Public Health Engineer Chief, Office of Ecology

cc: Kevin McGowin (Advanced Wastewater Solutions) Bryan McGowin (Advanced Wastewater Solutions) Scott Samuelson (Fuji Clean USA) Mike Dunn (Fuji Clean USA)



DIVISION OF ENVIRONMENTAL QUALITY Office of Ecology 360 Yaphank Avenue, Suite 2B, Yaphank NY 11980 P:(631) 852-5750 F:(631) 852-5812

Project Number: 2023.030.001

### DESIGN COMPUTATIONS FOR

Page 1 of 5

# CEN5/7 Precast Cover Slabs 10'-0" O.D.



# Advanced Wastewater Solutions Post Office Box 1622 Southampton, NY 11969





860 Hooper Road, Endwell, New York 13760 TEL: 607-231-6600 FAX: 607-231-6650 EMAIL: precast@delta-eas.com www.delta-eas.com



ACCEPTED BY THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES (DEPARTMENT) BASED ON INFORMATION PROVIDED BY ENGINEER.

SCDHS Approval No.: NS-003

The Department has reviewed this submittal for completeness and is hereby approved for use in Suffolk County. This approval is solely for the model(s), units(s) and/or structure(s) included in the engineering design drawings and calculations provided by the licensed design professional(s). Any changes or modifications to the approved design must be submitted for review and approval by the Department prior to its use in Suffolk County. The Department is not responsible for any errors, omissions, failures, construction defects or installation errors that may occur due to design professional, manufacturer, distributor or installer oversight or negligence.

1/20/2023 APPROVAL DATE

Ken Zegel, P.E.



SCDHS Approval for Use Page 2 of 5



JOB:	2023	.030.001 - Ad	dvanced V	Vastewater
DESCRIP	TION:	10' OD MH	Slab	
CULET		<b>e</b> f		

SHEET NO .:	of			
CALCULATED BY:	GAS	Date	1/12/23	
CHECKED BY:	Date			
CHECKED DI				





JOB: 2023	.030.001	- Advan	ced Wastewater	-
DESCRIPTION:	10' OD I	MH Slab		
SHEET NO .:	of			
CALCULATED BY	: GAS	Date	1/12/23	
CHECKED BY:	Da	ate		

Fax (607) 231-6650	
COVER SLAB DESIGN CONCENTRATED LIVE LOAD	
Wall Thickness = Slab Thickness = Earth Cover = Bar cover =	4.00 in 10.00 in 1.00 ft 2.00 in 1/4 Dia.
Impact =	1.30
Avg. Span (s) = Dead Loads: Soil = Concrete = Additional Uniform Dead Load = Total (wdl) =	One Way Slab     ## 14       8.47 ft     ## 14       0.12 ksf     ## 14       0.00 ksf     ••••••••••••••••••••••••••••••••••••
$\begin{aligned} & \text{Mdl=wdl } l^2 / 8 = \\ & e = 4 \text{.} 06S = \\ & p = (\text{Pw * Impact}) / e = \\ & \text{MII} = \text{ps } / 4 = \\ & \text{Mu} = \gamma [\beta(\text{L+I}) \text{*MII} + \beta \text{D*MdI}] = \end{aligned}$	4.51 ft (AASHTO 3.24.3.2) 4.61 kips/ft 9.76 kip-ft
'd' =	7.63 in
Req. Bar Size and Spacing Main Reinforcing: As = Distribution Steel=.As/Span^.5=	0.76 in.²/ft. Use #6 @ 7.0 in 0.26 in. sq/ft. Use #5 @ 14.0 in
ρ = As / b * d = ρ * n = <u>Flexure Check:</u> a = AsFy / 0.85f'cb =	0.00827703 0.06658366 1.114 in
$\phi Mn = \phi^* As^* Fy^* (d-(a/2)) = \frac{Cracking Check:}{k}$ $k = \sqrt{(2\rho n + \rho n^2) - \rho n} = 0$	
j = 1 - (k/3) = M = MdI + MII = fs = M / As j d = dc = A = 2 * dc * Spacing =	0.899 11.96 kip-ft 27.66 ksi <b>OK</b> 2.375 in 33.3 in <sup>2</sup>
$Z = fs^{3}\sqrt{(dc^{*}A)} =$	
Note: Shear considered satisfactory per AA	
Check minimum reinforcement requirement Note: Minimum As shall be at least 1/8 sq. i	s per AASHTO 8.17.1 n./ft (AASHTO 8.20.1) <u>∲Mn ≥ 1.2*Mcr</u> 7.91 kip-ft



JOB: 202	3.030.001 - /	Advan	ced Wastewate	r
DESCRIPTION:	10' OD MI	H Slab		
SHEET NO .:	of			
CALCULATED B	Y: GAS I	Date	1/12/23	
CHECKED BY:	Date	2		

COVER SLAB DESIGN CONCENTRATED LIVE LOAD	
Wall Thickness = 4.00 in	
Slab Thickness = <u>10.00 in</u> 1/4 Dia. ◀ ➡	
Earth Cover = 2.00 ft	
Bar cover = 2.00 in	
Impact = <u>1.20</u>	
One Way Slab $\begin{pmatrix} & & - \\ & & & \\ & & & \\ & & & \\ & & & &$	
One Way Slab	
Avg. Span (s) = $8.47$ ft	
Dead Loads: Soil = 0.24 ksf	
Concrete = 0.13 ksf	
Additional Uniform Dead Load = 0.00 ksf	
Total (wdl) = 0.37 ksf	
$Mdl=wdl l^2 / 8 = 3.27 kip-ft$	
e = 4+.06S = 4.51  ft (AASHTO 3.24.3.2)	
p = (Pw * Impact) / e = 4.26 kips/ft	
MII = ps / 4 = 9.01 kip-ft	
$Mu = \gamma[\beta(L+I)*Mll + \beta D*Mdl] = 23.82 \text{ kip-ft}$	
'd' = 7.63 in	
Req. Bar Size and Spacing	
Main Reinforcing: As = $0.76$ in. <sup>2</sup> /ft. Use #6 @ 7.0 in	
Distribution Steel=.As/Span^.5= 0.26 in. sq/ft. Use #5 @ 14.0 in	
$\rho = As / b^* d = 0.00827703$	
$\rho * n = 0.06658366$	
Flexure Check:	
a = AsFy / 0.85f'cb = 1.114 in φMn = φ*As*Fy*(d-(a/2)) = 24.09 kip-ft <b>ΟΚ</b>	
$\frac{\text{Gracking Check:}}{\text{Cracking Check:}} = 24.09 \text{ kip-it OK}$	
$k = \sqrt{(2\rho n + \rho n^2)} - \rho n = 0.304$	
j = 1 - (k/3) = 0.899	
M = MdI + MII = 12.28 kip-ft	
fs = M / As j d = 28.41 ksi OK	
dc = 2.375 in	
$A = 2 * dc * Spacing = 33.3 in^2$	
$Z = fs^{3}\sqrt{(dc^{*}A)} = 122 \text{ kips/in } OK$	
Note: Shear considered satisfactory per AASHTO 3.24.4	
Check minimum tripforcement requirements not AACUTO 9.47.4	
Check minimum reinforcement requirements per AASHTO 8.17.1 Note: Minimum As shall be at least 1/8 sq. in./ft (AASHTO 8.20.1)	
Note: Minimum As shall be at least 1/8 sq. In./It (AASHTO 8.20.1) $\phi Mn \ge 1.2^* Mcr$	
Mcr = 7.91  kip-ft	
1.2  Mor = 9.49  kip-ft <b>OK</b>	
·	