COUNTY OF SUFFOLK



STEVEN BELLONE SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF HEALTH SERVICES

GREGSON H. PIGOTT, M.D., M.P.H. Commissioner

August 31, 2023

Mr. John M. Spritzer III, P.E. Delta Specialty Precast Concrete Engineers 860 Hooper Road Endwell, NY 13760 Sent via e-mail: precast@delta-eas.com



Re: NS-009 990 Gallon HS-20 Pretreatment Tank

Dear Mr. Spritzer,

The Suffolk County Department of Health Services, Division of Environmental Quality, Office of Ecology has received and reviewed your design drawings and computations prepared for Advanced Wastewater Solutions., Project No. 2023.030.002, with your signature and sealed on 8/15/2023 for the "5'-8" x 6'-6" ID 990-Gallon Pretreatment Tank Designed for HS-20 Live Load".

Based on the information provided, the Department of Health Services approves the use of this 990 gallon tank in traffic areas with a maximum burial depth of 2.5-feet. A copy of this letter and the signed and sealed design report will remain on file in the Office of Wastewater Management for future reference.

If you have any questions, please do not hesitate to contact me at (631) 852-5811.

Sincerely,

Ken Zegel, P.E. Principal Public Health Engineer Chief, Office of Ecology

cc: John Sohngen, P.E. (SCDHS)
Vincent Ernst (Delta)
Kevin McGowin & Bryan McGowin (Advanced Wastewater Solutions)
Peter Mercurio (Coastal Pipeline Products)



DIVISION OF ENVIRONMENTAL QUALITY Office of Ecology 360 Yaphank Avenue, Suite 2B, Yaphank NY 11980 P:(631) 852-5750 F:(631) 852-5812

Project Number: 2023.030.002

DESIGN COMPUTATIONS FOR

Page 1 of 12

5'-8" Diameter x 6'-6" ID 990-Gallon Pretreatment Tank **Designed for HS-20 Live Load**



PREPARED FOR:

Advanced Wastewater Solutions Post Office Box 1622 Southampton, NY 11969

PREPARED BY:



860 Hooper Road, Endwell, New York 13760 TEL: 607-231-6600 FAX: 607-231-6650 EMAIL: precast@delta-eas.com www.delta-eas.com



ACCEPTED BY THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES (DEPARTMENT) BASED ON INFORMATION PROVIDED BY ENGINEER.

SCDHS Approval No.: NS-009


The Department has reviewed this submittal for completeness and is hereby approved for use in Suffolk County. This approval is solely for the model(s), units(s) and/or structure(s) included in the engineering design drawings and calculations provided by the licensed design professional(s). Any changes or modifications to the approved design must be submitted for review and approval by the Department prior to its use in Suffolk County. The Department is not responsible for any errors, omissions, failures, construction defects or installation errors that may occur due to design professional, manufacturer, distributor or installer oversight or negligence.


08/31/2023

APPROVAL DATE


Ken Zegel, P.E.

SPECIFICATIONS






Page 4 of 12






JOB: 2023.	030.002			
DESCRIPTION:	990 Gallo	on Pretr	eatment Tan	<
SHEET NO .:	of			
CALCULATED BY:	ARN	Date	5/9/23	
CHECKED BY:	Dat	te		



Precast Concrete Water and Wastewater Structures" – ASTM C890



JOB:	2023.	030.002			
DESCF	RIPTION:	990 Gall	on Pretr	eatment Tar	nk
SHEE	T NO.:	of			
CALCU	LATED BY:	ARN	Date	5/9/23	
CHECK	ED BY:	Da	ate		



JOB:2023.030.002DESCRIPTION:990 Gallon PretreatmentSHEET NO.:ofCALCULATED BY:ARNDate5/9CHECKED BY:Date	ent Tank /23
COVER SLAB DESIGN CONCENTRATED LIVE LOAD	
Wall Thickness = 4.00 in Slab Thickness = 6.00 in Earth Cover = 2.50 ft Bar cover = 1.50 in Impact = 1.20	9 ft
Avg. Span (s) = 5.29 ft	5.29 ft
Dead Loads: Soil = 0.30 ksf Concrete = 0.08 ksf	Ļ
Concrete = 0.08 ksf Additional Uniform Dead Load = 0.00 ksf	•
Total (wdl) = 0.38 ksf	
$\begin{split} & \text{Mdl=wdl} \ \text{I}^2 \ / \ 8 \ ^* \ (0.5) = \ 0.66 \ \text{kip-ft} \\ & e = 4 + .06S = \ 4.32 \ \text{ft} \ (\text{AASHTO } 3.24.3.2) \\ & p = (\text{Pw} \ ^* \ \text{Impact}) \ / \ e = \ 4.45 \ \text{kips/ft} \\ & \text{MII} = ps \ / \ 4 \ ^* \ (0.5) = \ 2.94 \ \text{kip-ft} \\ & \text{Mu} = \gamma [\beta(\text{L+I}) \ ^* \text{MII} + \beta \text{D} \ ^* \text{MdI}] = \ 7.24 \ \text{kip-ft} \\ & \text{Avg} \ \text{'d} = \ 3.88 \ \text{in} \end{split}$	
Req. Bar Size and Spacing	
	a. Dir.)
$\rho = As / b * d = 0.01131046$ $\rho * n = 0.09098574$	
Flexure Check:	
a = AsFy / 0.85f'cb = 0.773 in $\phi Mn = \phi^*As^*Fy^*(d-(a/2)) = 8.26 kip-ft OK$ <u>Cracking Check:</u>	
$k = \sqrt{(2\rho n + \rho n^2)} - \rho n = 0.345$	
i = 1 - (k/3) = 0.885	
j = 1 - (k/3) = 0.885 M = MdI + MII = 3.60 kip-ft	
M = MdI + MII = 3.60 kip-ft fs = M / As j d = 23.92 ksi OK	
M = MdI + MII = 3.60 kip-ft	

Note: Shear considered satisfactory per AASHTO 3.24.4


Check minimum reinforcement requirements per AASHTO 8.17.1 Note: Minimum As shall be at least 1/8 sq. in./ft (AASHTO 8.20.1) Mcr = 2.85 kip-ft1.2 Mcr = 3.42 kip-ft ОΚ




JOB: 20	23.030.002			
DESCRIPTION	1: 990 Gall	on Pretr	eatment Tank	(
SHEET NO	.: of			
CALCULATED	BY: ARN	Date	5/9/23	
CHECKED BY:	Da	ate		

WALL DESIGN


Height=	6.50 ft
Wall Thickness=	4.00 in
Inside Diameter=	5.67 ft
Outside Diameter=	6.33 ft
Average=	6.00 ft
Analyze compressive force at bottom of wall Compressive force 'P'=wdl/2= Compressive stress fc=P/A= Compressive stress allowable=.45f'c= Result= Minimum reinforcing required= ref ASTM C478, Art. 14.4.1.1	2.84 kips 59.15 psi 1800.00 psi OK 0.17 in.²/ft.



(Surcharge Applied Over Entire Height of Unit)




COMPRESSIVE FORCE



PRESSURE DIAGRAM



JOB: 2023.0	030.002			
DESCRIPTION:	990 Gall	on Pretr	eatment Tar	nk
SHEET NO .:	of			
CALCULATED BY:	ARN	Date	5/9/23	
CHECKED BY:	Da	ate		



CIALTY PRECAST CONCRETE END 0 Hooper Road, Endwell, NY delta-eas.com Phone (607) 231-6600 Fax (607) 231-6650	A DI SI CA	DB: 2023.030.002 SCRIPTION: 990 Gallon Pretreatment Tank HEET NO.: of LCULATED BY: ARN Date 5/9/23 ECKED BY: Date
Check Buoyancy		
Inside Diameter (D)5.67 ftInside Height (H)6.50 ftEarth Fill (F)0.00 ft	Wall Thickness4.Bottom Slab Thickness4.Water table depth (WT)0.	00 in Outside Dia. (OD) 6.33 ft 00 in 00 in Outside Height (OH) 7.33 ft 00 ft
Unit weight of Concrete (Wc) Unit weight of Soil (Ws) Unit weight of Water (Ww)	150 pcf Heig 120 pcf 62.4 pcf Safety Factor Req'	nt of Structure above grade (Hg) 0.00 ft d 1.50
Downward ForcesConcrete Weight $\pi OD^2 OH/4$ Weight of fill $\pi * OD^2/4*F$ Additional WeightSubtract for openings	*Ws =	64 lbs 0 lbs Ibs 62 lbs 02 lbs
<u>Upward Buoyant Force</u> π * OD ² /4*(OH+F-WT-Hg)*Ww =		<u>16 lbs</u> 14 lbs
Note: The safety factor is less t	Safety Factor 0.	68 < 1.50 NG Diution



JOB:	2023.0	30.002	<u>)</u>		
DESCRIP	TION: 9	90 Gal	lon Pretr	eatment Ta	ank
SHEET	NO.:	of			
CALCULA	TED BY:	ARN	Date	5/9/23	
CHECKED	BY:	D	ate		





JOB:	2023.	030.00	2		
DESCRIP	TION:	990 Ga	allon Pre	treatment	: Tank
SHEET	NO.:	of			
CALCULA	TED BY:	ARN	Date	5/9/23	
CHECKED	BY:		Date		

nside Diameter (ID) 5.67	ft Top Sla	ab Thickness	6.00 in	Outside Dia (OD)	6.33 ft
		nickness	4.00 in		
nside Height (Ht) 6.50	ft Bottom	Slab Thickness	4.00 in	Outside Height (OH)	7.33 ft
Earth Fill (F) 0.00	ft Water	able depth (WT)	0.00 ft	Base Extention =	4.00 in
Jnit weight of Concrete (Wc)	15	0 pcf	Height of Stru	ucture above grade (Hg)	0.00 ft
Jnit weight of Soil (Ws)	12	0 pcf		Base Slab Dia.(w/Ext.):	7.00 ft
Jnit weight of Water (Ww)	62.	4 pcf		Safety Factor Req'd	1.50
Downward Forces					
Concrete Weight πOD^2 (OH/4 - π ID ² H/4	+ * Wc =	10,064 lbs		
Weight of fill π * OD	² /4*F*Ws =		0 lbs		
Buoyant Weight of Base Exte	ension =		203.9 lbs		
Buoyant Weight of soil engage	ged by extensio	n =	2,815 lbs		
Additional Weight 0			0 lbs		
Subtract for openings			- 262 lbs		
Inward Ducyant Fares		Total	12,820 lbs		
<u>Upward Buoyant Force</u> τ * OD ² /4*(OH+F-WT-Hg)*W	w =		14,416 lbs		
		Difference	-1,595 lbs	_	
		Safety Factor	0.89 <	1.50 NG	
Consideration of Soil Wedge Additional Downward Forc	e Due to Soil V				
Assume an interface friction			conservative)		1.876 ft
Raduis of soil wedge @ surfa		3 ft @ 1/3 pt of Co		//////	
Perimeter of base extension	25.91		0.00ft		
Buoy. weight of soil wedge		1 lbs	\uparrow		
Add to downward force	<u>12,82</u> 22,62		6.50 ft		δ 7.00 ft
	22,02	1 105	0.50 1		/
Safety factor	1.57 >	1.50 OK			/
	1.07			la	4in